NOTICE.

Is hereby given that the exclusive privilege of vending Bagani Toddy in the Yedahalli sub-taluk, excluding Nerlkoppa village, and in Tarikere and Kadur taluks, for 1897-98, will be sold by public auction on the 15th December 1897, at the Chikmagalur Taluk Cutcherry by the General Assistant Commissioner in charge of Excise Department, Kadur district, subject to the conditions laid down in Government Notification No. 9873—Excise 352, dated 8th May 1897.

The price of Bagani Toddy is fixed by the Excise Commissioner as hereunder :—

Koppa kasaba and village shops.	*Kadur and Tarikere kasaba and village shops.*
One anna and six pies per seer (0-1-6.)	One anna and four pies per seer (0-1-4.)

T. WEIR, *Dy. Comr., Excise Dept.*

FRENCH ROCKS DIVISION.

The 24th November 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 14th December 1897, for completing the restoration of the Devaraya anikat across the River Cauvery in Seringapatam taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 9-30 A. M. and 5-30 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for completing the restoration of Devaraya anikat" in default of which, tenders will be rejected.

5. The first acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Dismantling and removing the old apron sujicut with jelly mixed with clay, &c.	C. yds.	2,175
Re-filling with the above stuff as packing	,,	1,355
Benching rock	S. ft.	4,535
Blasting rock	C. yds.	4
Excavating soft rock	,,	50
Stone in surki including barging and carting 3 miles lead	C. ft.	17,978
Hammer dressed stone in surki mortar including barging, carting, &c. ..	,,	9,381
Surki concrete	,,	16,116
Cement pointing	Sqr.	114·62
Burnt stone slabs set in surki	C. ft.	386
Baling water including ring bund, &c.	Lump sum.	

The 28th November 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 14th December 1897, for restoring the Girkahalli tank, Registered No. 67, Nagamangala taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 9-30 A. M. to 5-30 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for restoring Girkahalli tank, Registered No. 67, Nagamangala taluk," in default of which, tenders will be rejected.

5. The first acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	*Unit of work.*	*Rate per unit.*
Bund—		
Earthwork	C. yds.	17,640
Old stone work	,,	1,314
New stone work	,,	2,856
Grade stones	No.	25
Mile stones	,,	2
Tank No. stone	,,	1
Gauge stone	,,	1
Clearing jungle	Lump sum.	
Turfing	Sqr.	753·84
Waste weir right 135 ft. long—		
Excavation foundation in soft rock	C. yds.	231
Brick in surki mortar	C. ft.	10,205
Burnt stone slabs	,,	229
Plastering with surki mortar	Sqr.	35·45
New stone work	C. yds.	177
Old stone work	,,	100
Earthwork	,,	12

T. INMAN, *Executive Engineer.*

MYSORE DIVISION.

The 25th November 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 20th December 1897, for restoring and improving the Homma tank, Registered No. 36 of Chamrajnagar taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring and improving the Homma tank, Registered No. 36 of Chamrajnagar taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.	*Per.*	*Quantity.*	*Rate.*
Bund—			
Earthwork	C. yd.	45,003	
Turfing	Sqr.	27,881	
Rough stone revetment	C. yd.	1,340	
Fixing new grade stones with lead and edge stones ..	No.	72	
Gauge stone	,,	1	
Register number stone	,,	1	
B. M. stones	,,	2	
Clearing jungle	Lump sum.		
Waste weir—			
Extending weir	R. ft.	200	
Sluices—			
Examining and repairing New sluices	Lump sum.		
Distribution—			
Constructing an acqueduct	,,		
Supply—			
Improving feeder channel	,,		

C. A. MAHADEVA SASTRI, *Executive Engineer.*